



Construct drop kerbs and leave gap in bollards to provide a crossing for pedestrians

Existing gully to be maintained

mini-roundabout markings - RRM 033

Existing concrete build-out to be removed to proposed level and replaced with 100mm DBM

road signs - bolt down bollards at 1m centres

road signs - water filled barriers to form central island

road marking - 200mm wide white theroplastic - RRM 019

road marking - Yield marking white theroplastic - M 115

road marking - 100mm wide white theroplastic - RRM 021

Existing gully to be maintained

Proposed Galbally Rd roundabout plan - scale 1:200